Memphis Innovation Corridor Bus Rapid Transit

Tennessee Section Institute of Transportation Engineers (TSITE)

Spring Meeting - May 18, 2022





Kimley» Horn





About the Project - History

- MATA Short Range Transit Plan 2012
- Midtown Alternatives Analysis 2014
- Locally Preferred Alternative (LPA)

Bus Rapid Transit – Downtown to UofM (Adopted by MATA)


Board May 2017)


FTA Environmental Class of Action

Documented Categorical Exclusion (DCE)

Memphis 3.0 / Transit Vision Plan

TIGER and BUILD Grant Applications





About the Project

The Memphis Innovation Corridor will include the following features along the eight-mile corridor:

- Bus Rapid Transit vehicles arriving every 10 minutes during peak periods
- 16 modern transit stations/31 individual platforms
- Branded all-electric BRT vehicles
- Dedicated transit only lanes on B.
 B. King Boulevard and Second
 Street

- Roadway Improvements
- Green Infrastructure
- Upgrades to all traffic signals
- Pedestrian improvements
- Intersection improvements

Operating Plan

Frequency and Duration of Service



- Operating Policy
 - No flag stop service
 - Other fixed route buses to use Bus Only lanes
 - No bus passing in Bus Only lanes
- Fare Policy
 - Same as current fixed route service
















Features and Amenities – BRT Stations

- Real-Time Bus Arrival Information
- Security
 - Cameras
 - Emergency Call Box
- Off-Board Fare Collection
- Electronic signage and communications

Station Features (cont.)

- Level Boarding at 29 Transit
 Stations
- ADA tactile signage
- ADA voice announcements for next bus arrival
- Tactile strips at the boarding edge
- Bicycle and scooter parking areas
- Seating
- Concrete bus pads
- Opportunities for public art








Typical mConnect Station Medical Center – Union at Health Sciences Park







Typical mConnect Station Midtown - Union at Cooper Street






A.W. Willis Will Hudson Transit Center (Terminal) 2 2nd Street (Utbound) **Bus Only Lane** Location **Bus Shares General Purpose** Union Ave Lane


Transit Only Lanes


- B.B. King Blvd Northbound
- North 2nd Street
 Southbound



Project Description

Roadway/Safety Improvements








Project Description

- Traffic Signal Improvements
 - Signal reconstruction or modification
 - Transit Communications
 - ADA Improvements
 - Transit signal priority (TSP)
 - Advanced Traffic
 Management System (ATMS)


Traffic Signal Improvements



Why BRT and TSP?

Regular Bus Operations

BRT Bus Operations with TSP



Transit Signal Priority

 Passive Priority – Based on an optimal signal coordination, considering the transit operations / speeds


"Good Ole Fashioned Signal Timing Optimization"

- Active Priority Priority treatment following detection and subsequent priority request activation
 - Green Extension
 - Early Green
 - Actuated Transit Phases
 - Exclusive left turn transit only lane
 - Queue Jump (QJ) phase
 - Phase Insertion/Re-Service
 - i.e. Insertion of a leading left-turn-only phase for transit vehicles
 - Phase Rotation
 - Phase Omission / Skipping







Transit Signal Priority Process




Active Priority: Early Green




Active Priority: Early Green




Active Priority: Early Green








Queue Jump: Shared Lane Union Ave at Second St






Queue Jump: Shared Lane Union Ave at Manassas St




Queue Jump




Centralized TSP Architecture










Downtown Intersection Improvements

Reduced Pedestrian Crosswalks

- Improved Pedestrian Striping and Signals
- Bioswales
 - Low maintenance plantings
 - Maintenance Agreements





STUB 2-3" PVC N&W

















Test Platform

Project Funding

Total Planned Project Funding - \$94.6 Million



^{*} Funding amounts are subject to change



Environmental Clearance and Preliminary Engineering May 2019 - Feb 2021

Small Starts Grant Approval

January 2022

2019 2020 / 2021

2023 2024 2025 2026

Final Design May 2020 - Mar 2022

Construction: 2022-2026

 BUILD Grant Award Notification Nov 2019

Environmental Document **Approved** Feb 2021

Groundbreaking Oct 2022

mConnect Begins Service Spring 2026

